

Evaluation of the risk of *Legionella spp.* development in sanitary installations

K. Dinne, O. Gerin, B. Bleys, K. De Cuyper

Belgian Building Research Institute



Belgium

Content

1. Introduction
2. The BBRI test facility
 - 2.1 description test facility
 - 2.2 heat shock experiments
3. First results
4. Preliminary conclusions

1. Introduction

Why new Legionella research?

■ Energy context:

- *Reducing the energy needs for buildings is a European challenge in order to meet the 2020 requirements: all new buildings must be near zero energy buildings*
- *As the energy-use for space heating continues to diminish, energy-use for domestic hot water (DHW) becomes increasingly relevant*
- *Efficient design of DHW installations becomes ever more important*
- *Pressure to reduce DHW production temperatures in certain types of installations (installations with heat pumps, low district heating, etc.)*

■ Hygienic context:



- *Having a good water quality at the faucet is essential, and certainly more important than energy related aspects*
- *Risks of lower DHW production temperatures with regular thermal shocks have not been studied in detail*

1. Introduction (2)

What are we doing at BBRI?

- Evaluation -on a full scale test facility- of the possibility to reduce the DHW production temperature without increasing risk of Legionella development
- The test facility consists of:
 - 200 l water tank
 - ~ 40m circulation loop
 - 2 draw-off pipes (bathroom and kitchen)
 - Single family tapping profile: 156 l/day
- DHW at 45°C with regular heating to 60°C
- Monitoring of Legionella concentration in water and biofilm

2. The BBRI test facility



2. The BBRI test facility (2)

■ Culture tank:

- 200 l
- Temperature: 39°C
- Daily draw-off of 127 l
- Stable concentration of $2 \cdot 10^5$ cfu/L

■ “test” tank:


- 200 l
- Temperature: 45°C
- Daily tapping profile
- Heating element: vertical electrical resistance (6 kW)
- Thermocouples on outside wall

■ Circulation loop:

- Vertical pipes: DN32 with DN16 recirculation
- PEX-Alu-PEX with PIR insulation

2. The BBRI test facility (3)


« test » tank



	Distance from bottom (cm)
Temp. sensor n°5 :	122.4
Temp. sensor n°4 :	95.2
Temp. sensor n°3 :	68
Temp. sensor n°2 :	40.8
Temp. sensor n°1 :	13.6
Temp. sensor n°0 :	0


2. The BBRI test facility (4)

60°C/ 1h



2. The BBRI test facility (5)

Biofilm monitoring



2. The BBRI test facility (6)

Tap schedule		DHW Flow-rate	Tap duration	Tapped DHW volume
Start hour	Type of draw-off	l /min	s	liters
06:59	purge of the shower pipe	6.5	10	1.083
07:00	Shower n° 1	6.5	355	38.5
07:10	Shower n° 2	6.5	393	42.6
08:00	Shower n° 3	6.5	296	32.1
12:00	Kitchen faucet	5	6	0.50
12:30	Kitchen faucet	5	20	1.67
13:45	Kitchen faucet	5	30	2.50
18:15	Children's bath (40 L)	6.5	311	33.7
19:00	Kitchen faucet	5	6	0.50
19:15	Kitchen faucet	5	3	0.25
20:00	Kitchen faucet	5	30	2.50
Total tapped daily DHW Volume :				155,79 l

2. The BBRI test facility (7)

Heat shock experiments

weeks	T production (tank)	T heating (thermal shock)	Heating duration	Frequency	Number of thermal shocks
1 and 2	45 °C	60 °C	30 min	1x / week	2 shocks
3 and 4	45 °C	60 °C	1 h	1x / week	2 shocks
5	45 °C	60 °C	30 min	1x / week with extra circulation on tank	1 shock
6 and 7	45 °C	60 °C	1 h	1x / week with extra circulation on tank	2 shocks
8 and 9	45 °C	60 °C	1 h	1x / week with extra circulation on tank. + 30 minutes thermal disinfection of the sampling taps	2 shocks

2. The BBRI test facility (8)


Heat shock experiments

weeks	T production (tank)	T heating (thermal shock)	Heating duration	Frequency	Number of thermal shocks
10	45 °C	60 °C	Warming up +4 x 30 min (for taps disinfection)	1x / week with extra circulation on tank. + 4 x 30 minutes thermal disinfection for each of the sampling taps and draw-off pipes	1 shock
11	45 °C	60 °C	Warming up +30 min (for tank) + 4 x 30 min (for taps disinfection)	1x / week with extra circulation on tank. + 4 x 30 minutes thermal disinfection for each of the sampling taps and draw-off pipes	1 shock
14-18	45 °C	60 °C	1 h	2x / week with extra circulation on tank	9 shocks
19	45 °C	60 °C	1 h	7x /week with extra circulation on tank	7 shocks

3. First results

■ In the test facility:

None of the thermal shocks lead to acceptable Legionella concentrations (< 1000 cfu/l) in the DHW installation



3. First results (2)

- Heating of watersamples in laboratory taken from the test facility:
 - at **65°C** *no* Legionella ***bacteria survived***, even if the thermal shock only lasted **5 min**.
 - At **60°C** for **60 min**, Legionella concentration decreased from 100.000 cfu/l to 250 cfu/l. ***Cultivable bacteria remained.***

- Biofilm monitoring:
 - Progressive decrease (from $3.3 \cdot 10^6$ to $2.5 \cdot 10^3$ cfu/l) of the Legionella concentrations
 - After 15 days without thermal shock: return to initial concentration

4. Preliminary conclusions

- Important to standardise sampling methodology and to disinfect the sampling points
- In a contaminated installation, with ***DHW production temperature of 45°C, a regular thermal shock at 60°C seems insufficient*** to stabilise the Legionella concentration below 1000 cfu/L
- As laboratory tests are promising with shocks at 65°C and 70°C, more combinations will be studied:
 - Higher thermal shock temperature, duration and frequency
 - Higher DHW production temperature (50°C, 55°C)
- Test will be continued till September 2018

**Thank you
for your attention**

